Sl. No	Description of item
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw u meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disp earth to be leveled neatly after breaking of clods complete as per specifications
2	Grading- I Material Construction of granular sub-base by providing close graded material, mixing mechaical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers motor grader on prepared surface and compacting with vibratory power roller to achieve the de density, complete as per specifications. A. Plant Mix Method.
3	Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifica including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed meth tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surfac compacting with vibratory roller to achieve the desired density complete as per specifications.
4	Providing and applying tack coat on granular base such as WBM and WMM surfaces hot bitumen pr at 4 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surf including cost of all materials, labour, HOM of machineries complete as per specifications.
5	Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producir average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying w hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MO specification clause No. 500.8 complete in all respects as per specifications.
6	Carriage of Mixed Materials 10kms for Item of SI NO.1 C) Rs. 5.20 per cumKM